

wing are taken over from the plan and cut out from the balsa sheets. I have first made the trailing edges, carved the slots for the ribs and fixed them on the building plan.

I have then positioned all the ribs into the slots of the trailing edge. I have used a steel ruler positioned upwards on the top of the ribs at different positions along the wing to identify the ribs that needed to be trimmed (sanded), as they showed some differences in height.

The notes on the plan mentions that ribs are oversized and need some trimming. So, that's correct.

If the ribs are now all trimmed apart from the leading and trailing areas, that will come later after the leading edge has been made and joint to the ribs first.











